

Rehabilitation of Korogwe - Same Road, Lot 1, Section Korogwe - Mkumbara

Facts

City/Country

Korogwe / Tanzania

Client

The Chief Executive, TANROADS Tanzania
Nat. Roads, Dar Es Salaam

Contract Value

€45,63 Mio.

Construction Period

03/2012 - 10/2014 (32 Months)

Project Description

The existing road was a bitumized rural road connecting Dar Es Salaam with Arusha + Nairobi (76 km). The rehabilitation comprised the widening of the alignment, construction of drainage facilities, reconstruction of the existing pavement and the rehabilitation of the Mombo bridge. Stabilization of the subbase course between km 0+18 and between km 43+76. Between km 18+43 a crushed aggregates base course was executed. Material for the base course, the asphalt pavement and the aggregates for the concrete were excavated and processed from the own quarry. The project was financed by the International Development Association a Worldbank Fund. The completed Project was handed over to the Employer by end 2014.

403,060 m³ - Earthworks

140,000 m³ - Crushed Based Course

35,000 m³ - Asphalt

109,430 m³ - Construction of cement treated subbase + base

40,848 m³ - Laying of bituminous material

4,480 m³ - Concrete works

