

REHABILITATION OF THE RUHENGERI - GISENYI ROAD

Facts

City/Country

Ruhengeri - Gisenyi / Rwanda

Client

Ministère des Infrastructures & de la
Planification Economique, Kigali

Contract Value

€46,05 Mio.

Construction Period

7/2007 - 3/2010 (33 months)

Project Description

Rehabilitation of the paved road between Ruhengeri and Gisenyi (64.6 km), town roads in Gisenyi (2.2 km) and access road to Rwanda border (5.3 km). The project also included the determination of centreline data and levels.

PROJECT DATA:

Forest clearance of shoulders	
Removal of boulder	
Construction of support structures	
Removal of existing pavement	450,000 m ²
Earthworks	321,136 m ³
Execution and/or improvement of existing sub-base	190,000 m ³
Reinforcement of shoulders	
Crushed stone base course 0/31.5	101,000 m ³
Bituminous wearing course 5 cm	530,000 m ² (= 26,576 m ³)
Single seal surface treatment	229,000 m ²
Surface dressing of shoulders	263,000 m ²
Concrete works	6,292 m ³
Drainage works	
Road markings and furniture	

